

FIELD FLOOR IMPACT INSULATION TEST REPORT

U1509, 12 CUNNINGHAM STREET, NEWSTEAD



24 Mexicanus Drive PO Box 790 Park Ridge Queensland 4125 Australia p. +61 7 3802 2155 hasitha@palmeracoustics.com www.palmeracoustics.com

Commissioned by: Flooring Distributors of Australia (FDA)

Date: 13 June 2023

Project number: 5835 **Version:** V.0

Author: Eric Huang





DOCUMENT INFORMATION							
Author: E	Author: Eric Huang Approved by: Ross H. Palmer						
Date : 13 June 2023		Date:	13 June	2023			
	VERSION HISTORY						
Version	Description	Date	Autho	r	Approved by		
V.0	Final	13-06-2023	Eric Huang		Ross H. Palmer		
DOCUMENT DISTRIBUTION							
Сору	Name/Company	Hard Copy		El	Electronic Copy		
01	Flooring Distributors of Australia (FDA)			$\overline{\checkmark}$			
02							
03							
04	-						
05							



FIELD FLOOR IMPACT INSULATION TEST REPORT U1509, 12 CUNNINGHAM STREET, NEWSTEAD

TITLE Field Floor Impact Insulation Test

U1509, 12 Cunningham Street, Newstead,

QLD 4006 Test Report

TESTS BY Eric Huang

Senior Engineer - Palmer Acoustics (Australia) Pty Ltd

TEST DATE 12 June 2023

REPORT DATE 13 June 2023

TEST LOCATION Level 15 U1509 Living area to Level 14 U1409 Living area

FOR Flooring Distributors of Australia (FDA)



CONTENTS

1.0	INTRODUCTION	. 1
2.0	EQUIPMENT AND PROCEDURES	. 1
2.1	Measurement Procedures	. 1
2.2	Instrumentation	. 2
3.0	DESCRIPTION OF ROOMS	. 2
4.0	RESULTS	.3
5.0	CRITERIA ERROR! BOOKMARK NOT DEFINE	D.
6.0	CONCLUSIONS ERROR! BOOKMARK NOT DEFINE	D.
APPE	NDIX A	. 4
APPE	NDIX B	. 6
APPEI	NDIX C	7



1.0 INTRODUCTION

Flooring Distributors of Australia (FDA) has engaged Palmer Acoustics to perform a field impact insulation test at U1509, 12 Cunningham Street, Newstead. For this test, we use an ISO 140 standard tapping machine (per ISO 16283-2: 2020(E)).

Floor systems tested:

- Test 1 Concrete Slab U1509 Living Area to U1409 Living Area
- Test 2 Paramount Wood 5mm loose laid U1509 Living Area to U1409 Living Area
- Test 3 Paramount Wood 5mm + Regupol Multi Sonus 3mm U1509 Living Area to U1409 Living Area

2.0 EQUIPMENT AND PROCEDURES

2.1 Measurement Procedures

Testing conformed to ISO 16283-2:2020 "Field measurement of impact sound insulation of floors". Evaluation of the results to derive the single figure L'nT,w rating was conducted to ISO 717-2 2020 "Rating of insulation in buildings and of building elements – Part 2 Impact Sound Insulation".

Ambient sound levels were measured before testing.

The receiving room reverberation times were measured at various locations throughout the space, using the balloon-burst impulse test method, with the results averaged.

The Receiving room tapping sound levels were measured for 30 seconds at various locations throughout the space, with the results averaged.

Test results were analysed per ISO 16283 and ISO 717.



2.2 Instrumentation

The following instruments were used:

- Norsonics Nor140 Sound Analyser (serial number 1403252)
- B & K Tapping machine Type 3207 (serial number 2574503)
- B & K 4231 Calibrator (serial number 2153030)

Before and after each measurement session, the equipment was field calibrated and was within 0.2dB of the reference signal. All instruments hold a current calibration certificate from a NATA accredited calibration laboratory.

3.0 DESCRIPTION OF ROOMS

All windows and doors were closed in the source and receiving rooms.

Transmitting Room (Level 15 U1509 Living area)

Walls: Plasterboard;

Floor: Concrete slab with Carpet and test sample;

Room finish: Furnished.

Receiving Room (Level 14 U1409 Living area)

Slab Concrete; Walls: Plasterboard;

Ceiling: Suspende Plasterboard;

Floor: Carpet/Tiles; Room finish: Furnished.





Figure 1: Testing at U1509, 12 Cunningham Street, Newstead.

4.0 RESULTS

Our tests give the following results:

Table 1: Test Result Summary – Floor impact tests

	Test System	L'nT,w
1.	Bare slab – U1509 Living Area to U1409 Living Area	63
2.	Paramount Wood 5mm loose laid – U1509 Living Area to U1409 Living Area	53
3.	Paramount Wood 5mm + Regupol Sonus Multi 3mm – U1509 Living Area to	46
	U1409 Living Area	40

Appendix C contains the Test Certificates detailing the 1/3 octave band results for this report in terms of L'nT,w following ISO 717 - 2: 2020.

L'nT,w is a term used in the Building Code of Australia (BCA - see Appendix A) and represents a corrected room noise level, with a lower number showing better performance.

Qualification

The test results above <u>are specific to this test</u> and cannot be directly applied to any other location or flooring system. When applied to another floor, Palmer Acoustics can advise on the possible performance, but this must be in consultation with our office.

Author:

ERIC HUANG CPEng RPEQ

Senior Engineer

Approved by:

ROSS H. PALMER CPEng RPEQ 3534

Principal Engineer



APPENDIX A

GLOSSARY

IMPACT MEASUREMENT AND ASSESSMENT DESCRIPTORS

- *L*_{Aeq,T} Time average A-weighted sound pressure level is the average energy equivalent level of the A-weighted sound over a period "T".
- L_{Aeq} Equivalent Continuous Noise Level. The noise level in dB(A) which, if present for the entire measurement period, would produce the same sound energy to be received as was actually received as a result of a signal which varied with time. Normally abbreviated to "L_{eq}" or "L_{Aeq}", often followed by a specification of the time period (such as 1 hour or 8 hours) indicating the period of time to which the measured value has been normalised;
- $L'_{nT,w}$ Weighted Standardised impact sound pressure level; a measurement of impact sound transmission between rooms. Lower values denote better performance. The single figure measure is derived by adapting a standard response curve to measured 1/3 octave band sound pressure levels. Measured results are adjusted based upon a reverberation time of 0.5 sec in receiving room. Normally derived from a field test.
- $L'_{n,w}$ Weighted Normalised impact sound pressure level; a laboratory measurement of impact sound transmission between rooms. Lower values denote better performance. The single figure measure is derived by adapting a standard response curve to measured 1/3 octave band sound pressure level measurements. Measured results are adjusted based on the absorption of 10m^2 in the receiving room. Normally derived from a laboratory test.
- *Ci* A spectrum adaptation term compensating for the effect of floor coverings when applied to bare floors under test. The usually negative value, in decibels, is added to the single-number quantity, L'_{nw} or L'_{nTw}.
- *Impact Sound Pressure Level (L)* the average sound pressure level in a specified frequency band produced in the receiving room by the operation of the standard tapping machine on the floor assembly, averaged over each of the specified machine positions.
- L'_{nT} *Standardised Impact Sound Pressure Level* the impact sound pressure level standardised to a room with a reference reverberation time of 0.5 seconds.
- *L'n Normalized Impact Sound Pressure Level* the impact sound pressure level normalised to reference absorption area of 10 metric sabins (108 sabins).
- *Receiving Room* a room below or adjacent to the floor specimen under test in which the impact sound pressure levels are measured.
- *Source Room* the room containing the tapping machine.



STANDARDS

• ISO 16283 – 2

Acoustics – Field measurement of sound insulation in buildings and of building elements – Part 7: Default procedure for sound pressure level measurement

• ISO 717 – 2

Acoustics – Rating of sound insulation in building and of building elements – Part 2: Impact sound insulation

• ISO 3382-2:2008

Acoustics – Measurement of room acoustic parameters — Part 2: Reverberation time in ordinary rooms.



APPENDIX B

CALCULATION METHODOLOGY - L'nT,w

Correction to the signal level for background noise - ISO 16283-2:2015

If
$$(L_{\rm sb}-L_{\rm b}) > 10$$
, then $L = L_{\rm sb}$
If $10 > (L_{\rm sb}-L_{\rm b}) > 6$, then $L = 10 \log \left(10^{\frac{L_{\rm sb}}{10}} - 10^{\frac{L_{\rm b}}{10}}\right)$
If $6 > (L_{\rm sb}-L_{\rm b})$, then $L = L_{\rm sb} - 1.3$

L is the adjusted signal level, in decibels;

 $L_{\rm sb}$ is the level of signal and background noise combined, in decibels; $L_{\rm b}$ is the background noise level, in decibels.

Standardised impact sound pressure level - ISO 16283-2:2015

$$L'_{\mathrm{n}T} = L_{\mathrm{i}} - 10 \log \left(\frac{T}{T_{\mathrm{o}}}\right)$$

 L'_{nT} is the standardised impact sound pressure level;

 L_i is the impact sound pressure level;

T is the reverberation time in the receiving room;

 T_0 is the reference reverberation time in the receiving room; for dwellings, $T_0 = 0.5$ s.

Method of comparison - ISO 717-2:2013

To evaluate the results of a measurement of L'_{nT} in one-third-octave bands, the reference curve is shifted in increments of 1 dB towards the L'_{nT} curve until the sum of unfavourable deviations is as large as possible but not more than 32.0 dB.

An unfavourable deviation at a particular frequency occurs when the results of measurements exceed the reference value. Only the unfavourable deviations are taken into account.

The value, in decibels, of the reference curve at 500 Hz, after shifting in accordance with this procedure is $L'_{nT,w}$.



APPENDIX C

Test certificates (3)





FIELD IMPACT SOUND INSULATION - TEST CERTIFICATE

Test 1 of 3

Bare Slab

PROJECT: PN5835 U1509 Cunnigham Street, Newstead

Test Location: Level 15 U1509 Living to Level 14 U1409 Living Meas. Date: 12-Jun-2023

Meas. Parameter: LLeq

Client: Flooring Distributors of Australia (FDA) Tapping Machine: B&K, Type 3207

Test Performed: Eric Huang **Receiving Room Volume:** 103 m³

DESCRIPTION OF FLOOR AND SPECIMEN

Bare Slab

No. of Source posn: 2

Mic. posn: 2 sweeps

RT meas: 6 Imp.

Underlay: SLM: Nor 140

Adhesive:

Test Surface:

Ceiling: Suspended plasterboard

Slab: Concrete


Weighted Standardized Impact SPL


Results standardized to a RT of 0.5 seconds

Γ,w

63

ISO 16283-2:2015 & 717-2:2013





24 Mexicanus Drive Park Ridge QLD 4125

Ph (617) 3802 2155 www.palmeracoustics.com





FIELD IMPACT SOUND INSULATION - TEST CERTIFICATE

Test 2 of 3

Paramount Wood 5mm loose laid

PROJECT: PN5835 U1509 Cunnigham Street, Newstead

Paramount Wood 5mm loose laid

Test Location: Level 15 U1509 Living to Level 14 U1409 Living Meas. Date: 12-Jun-2023

Meas. Parameter: LLeq

Client: Flooring Distributors of Australia (FDA) Tapping Machine: B&K, Type 3207

Test Performed: Eric Huang **Receiving Room Volume:** 103 m³

DESCRIPTION OF FLOOR AND SPECIMEN No. of Source posn:

Mic. posn: 2 sweeps

RT meas: 6 Imp.

Underlay: SLM: Nor 140

Adhesive: Loose laid

Test Surface:

Ceiling: Suspended plasterboard

Slab: Concrete


Weighted Standardized Impact SPL

Results standardized to a RT of 0.5 seconds

L'nT,w

53

ISO 16283-2:2015 & 717-2:2013



24 Mexicanus Drive Park Ridge QLD 4125

Ph (617) 3802 2155 www.palmeracoustics.com





FIELD IMPACT SOUND INSULATION - TEST CERTIFICATE

Test 3 of 3

Paramount Wood 5mm

Regupol Souns Multi 3mm

PROJECT: PN5835 U1509 Cunnigham Street, Newstead

Test Location: Level 15 U1509 Living to Level 14 U1409 Living Meas. Date: 12-Jun-2023

Meas. Parameter: LLeq

Client: Flooring Distributors of Australia (FDA) Tapping Machine: B&K, Type 3207

Test Performed: Eric Huang **Receiving Room Volume:** 103 m³

DESCRIPTION OF FLOOR AND SPECIMEN

Paramount Wood 5mm

No. of Source posn: 2
Mic. posn: 2

2 sweeps

RT meas:

eas: 6 Imp.

Regupol Souns Multi 3mm SLM: Nor 140

Adhesive: Loose laid

Test Surface:

Underlay:

Ceiling: Suspended plasterboard


Slab: Concrete

Weighted Standardized Impact SPL

Results standardized to a RT of 0.5 seconds

46

ISO 16283-2:2015 & 717-2:2013



24 Mexicanus Drive Park Ridge QLD 4125

Ph (617) 3802 2155 www.palmeracoustics.com

palmer acoustics AU, TH & VN Acoustics and Audio Visual - Consulting Engineers